

**SMOKE GUARD® SYSTEM**

**MODEL 400  
SPECIFICATION**

Smoke Guard, Inc.  
287 N. Maple Grove  
Boise, ID 83704

Toll Free: 800.574.0330

Fax: 208.376.1600

e-mail: [info@smokeguard.com](mailto:info@smokeguard.com)

website: <http://www.smokeguard.com/>

MasterFormat 2005™ Location:

Recommended location under the current MasterFormat™ 2004 is Section 08 3483 Elevator Door Smoke Containment System.

CSI does not recommend the Division 07 location 07 8700 Smoke Containment Barriers since this is for static smoke containment systems. Smoke Guard products are active smoke containment systems of operable doors tied into fire and smoke alarms systems very similar to overhead coiling fire doors.

This recommendation has been vetted by a number of nationally recognized MasterFormat™ experts, active specification consultants, and the staff of CSI involved with maintaining MasterFormat™.

**SECTION 08 3483**

**ELEVATOR DOOR SMOKE CONTAINMENT SYSTEM**

**PART 1 - GENERAL**

**1.01 SUMMARY**

- A. Section Includes: Smoke detector activated elevator door smoke containment screen and control system designed to provide a tight-fitting, smoke- and draft-control assembly.
- B. Products Supplied But Not Installed Under This Section:
  - 1. End-of-line diode (3.9V, 2W). Installed at smoke detector to monitor the circuit.
- C. Related Sections:
  - 1. 09 2200–Non-Load Bearing Wall Framing: Metal backing in housing mounting area.
  - 2. 09 9100–Paints: Field painting of specified components; repainting of existing field painted elevator door frames.
  - 3. 28 3000–Detection and Alarm: Provision of smoke detectors.
  - 4. 14 2100–Electric Traction Elevators.
  - 5. 14 2400–Hydraulic Elevators.
  - 6. Division 26 Sections for 120VAC and control circuit power including conduit, boxes, conductors, wiring devices, and emergency power.

## 1.02 REFERENCES

- A. ASTM A240/240M – Standard Specification for Heat Resisting Chromium and Chromium-Nickel Stainless Steel Plate, Sheet and Strip for Pressure Vessels.
- B. ICC Evaluation Service ES AC77 – Acceptance Criteria for Smoke-Containment Systems Used With Fire-Resistive Elevator Hoistway Doors and Frames.
- C. ICC Evaluation Service report ESR-1136
- D. NFPA Codes and Standards:
  - 1. 70 – National Electrical Code.
  - 2. 105 – Recommended Practice for the Installation of Smoke-Control Door Assemblies.
  - 3. 72-2002 and 2007 – National Fire Alarm Code
- E. International Building Code:
  - 1. 2006 – Section 707.14.1
  - 2. 2009 – Section 708.14.1
  - 3. 2012 – Section 713.14.1
  - 4. 2015 - Section 3006.1
  - 5. 2018 – Section 3006.1
- F. UL Standards:
  - 1. 268 – Smoke Detectors for Fire Protective Signaling Systems.
  - 2. 508 – Industrial Control Equipment.
  - 3. 864 – Control Units for Fire Protective Signaling Systems.
  - 4. 1784 – Air Leakage Tests for Door Assemblies.

## 1.03 SUBMITTALS

- A. Reference Section 01 3300–Submittal Procedures; submit following items:
  - 1. Product Data.
  - 2. Shop Drawings: Include door width and height, jamb width, jamb and head projection, screen width, mounting height, and housing width. Show and identify related work performed under other sections of the specifications.
  - 3. Quality Assurance/Control Submittals:
    - a. Qualifications:
      - 1) Proof of manufacturer qualifications.
      - 2) Proof of Installer qualifications.
    - b. Certifications: Copy of specified items.
    - c. Manufacturer’s installation instructions and testing procedures

## 1.04 CLOSEOUT SUBMITTALS

- A. Comply Section 01 7700–Closeout Submittals; submit following items:
  - 1. Operation and Maintenance [Manual] [Video]
  - 2. Manufacturer’s Warranties

## 1.05 QUALITY ASSURANCE

- A. Overall Standards:
  - 1. Manufacturer shall maintain a quality control program in accordance with ICC-ES Acceptance Criteria 77.

- B. Qualifications:
  - 1. Manufacturer Qualifications: Minimum seven years experience in producing smoke containment systems of the type specified.
  - 2. Installer Qualifications: Factory trained by manufacturer.
- C. Certifications:
  - 1. Manufacturer's ICC Evaluation Service report ESR-1136.
  - 2. California Department of Forestry and Fire Protection and Office of the State Fire Marshal Listing.
  - 3. Testing Laboratory Label.
  - 4. UL Listing.
  - 5. OSHPD Anchorage Pre-Approval No. OPM-0233-16
- D. Pre-Installation Meeting:

*Include painting sub-contractor in following paragraph if new or existing elevator door frames or auxiliary rails will be field painted.*

- 1. Schedule and convene a pre-installation meeting prior to commencement of field operations with representatives of the following in attendance: Owner, Architect, General Contractor, smoke containment system sub-contractor, painting sub-contractor, and electrical sub-contractor.
- 2. Review substrate conditions, requirements of related work, installation instructions, storage and handling procedures, and protection measures.
- 3. Keep minutes of meeting including responsibilities of various parties and deviations from specifications and installation instructions.

#### 1.06 DELIVERY, STORAGE, AND HANDLING

- A. Reference Section 01 6600–Product Storage and Handling Requirements.
- B. Follow manufacturer's instructions.

#### 1.07 WARRANTY

- A. Provide manufacturer's standard one year warranty.
- B. Maintenance and Testing:
  - 1. Perform minimum semi-annual maintenance and testing on each smoke containment system as required by the manufacturer's warranty, code agency evaluation reports, and as required by local authority having jurisdiction.
  - 2. Provide test documentation.

### **PART 2 - PRODUCTS**

#### 2.01 MANUFACTURER

- A. Model 400
- B. Manufacturer:
  - 1. Smoke Guard, 287 Maple Grove, Boise, Idaho 83704 <http://www.smokeguard.com/>
  - 2. Distributor:

*Insert name, address and phone numbers of local distributor below. Local distributor can be found at [www.smokeguard.com](http://www.smokeguard.com)*

- C. Label each smoke containment system with following information:
  - 1. Manufacturer's name.
  - 2. Maximum leakage rating at specified pressure and temperature conditions.
  - 3. Label of quality control agency.

## 2.02 PERFORMANCE REQUIREMENTS

- A. Air Leakage: Not to exceed 3 cfm (0.001416 m<sup>3</sup>/s) per sf of door opening at 0.1 in (25 Pa) water pressure differential at ambient temperature and 400 degrees F (204 degrees C) tested per IBC 2009 714.2.3.

## 2.03 COMPONENTS

- A. Screen:
  - 1. Film: Minimum 1 mil (0.025 mm) thick transparent polyimide film reinforced with minimum 100 denier Nomex yarn at .25 in (6.35 mm) each way.
  - 2. Magnetic Strips: Flexible multi-pole strips attached to longitudinal edges of film with adhesive tape.
- B. Housing: 20 gage, powder coated, cold rolled steel container with dust cover and door with concealed hinges. Housings are 55, 64, or 73" in length plus 1-1/2 inches for a junction box on the left side.
- C. Self-contained control system within the housing – no remote mounting of control boxes and associated wiring to the control boxes shall be allowed.

*Following auxiliary rails are required for elevator door frames that are non-ferrous (e.g. stainless steel, brass, bronze, aluminum) or do not have a flat 2 inch (50 mm) wide face, or are recessed in or flush with the finished wall surface.*

*if painting of rails is required, include following fielding requirement in section 09 9100:*

*Paint must be heat resistant to 300 degrees f (149 degrees c) and be spray applied, maximum 5 mils (.13 mm) thick including primer.*

- D. Auxiliary Rails:
  - 1. Material: 16 gage ASTM A 240/240M, Type 430, ferritic stainless steel.
  - 2. Size: 2 inches (51 mm) wide; 1 inch (25 mm), 3/4 inch (19 mm) or 1/2 inches (13 mm) deep, depth as required to project beyond face of elevator door frame, as shown in Shop Drawings.
- E. Rewind Motor: NFPA 70, 90v DC.
- F. Release Mechanism: Comply with UL Standard No. 864.
- G. Screen Rewind Switch: An on screen switch to rewind screen into housing shall be required.

### **PART 3 - EXECUTION**

#### **2.04 EXAMINATION**

- A. Examine substrates upon which work will be installed.
  - 1. Verify related work performed under other sections is complete and in accordance with Shop Drawings.
  - 2. Verify wall surfaces and elevator door frames are acceptable for installation of smoke containment system components.
  - 3. Verify existing field painted elevator door frames to be used for screen adherence have been repainted in accordance with smoke containment system manufacturer's instructions or they have the original factory paint.
- B. Coordinate with responsible entity to perform corrective work on unsatisfactory substrates.
- C. Commencement of work by installer is acceptance of substrate.

#### **2.05 INSTALLATION**

*Manufacturer's installation instructions cover procedures for normal installation and assume the design and detailing complies with smoke guard system requirements. Unusual conditions or variations from Smoke Guard system requirements should be added to this article.*

- A. Install smoke containment system components in accordance with manufacturer's installation instructions.

#### **2.06 FIELD QUALITY CONTROL**

- A. Field Test: Follow manufacturer's cycle test procedures.
  - 1. Notify Owner's Representative, local Fire Marshal, alarm sub-contractor and [elevator sub-contractor] [elevator service company] minimum one week in advance of scheduled testing.
  - 2. Complete maintenance service record.

#### **2.07 DEMONSTRATION**

- A. Demonstrate required testing and maintenance procedures to Owner's Representative.
- B. Maintenance and Testing:
  - 1. Perform minimum semi-annual maintenance and testing on each smoke containment system as required by the manufacturer's warranty, code agency evaluation reports, and as required by local authority having jurisdiction.
  - 2. Retain permanent record of tests.
- C. Future Painting: Paint elevator door frame and/or auxiliary rails in accordance with Operation and Maintenance Manual.
- D. Qualified Smoke Guard Inspector assesses unit(s) after exposure to a fire event.

END OF SECTION